

**ADDENDUM NO. 1 TO THE CONSTRUCTION DOCUMENTS FOR:**

**LOCK HAVEN UNIVERSITY # 409-NP  
EAST CAMPUS CLASSROOM HVAC REPLACEMENT  
W2A Project No. 10002**

**PREPARED BY: W2A DESIGN GROUP  
609 Hamilton Street Suite 200  
Allentown, PA 18101**

**DATE: 19 APRIL 2010**

The following amendments, additions, deletions and corrections are hereby made to the Contract Documents dated 30 March 2010 for this project. References to the drawings contained herein are described sufficiently for bidding purposes. BIDDER - ACKNOWLEDGE RECEIPT OF ADDENDUM ON THE BID FORM.

**HIGHLIGHTS OF KEY ADMINISTRATIVE ITEMS** were reviewed and are available for reference at the LHUP Purchasing website: [www.lhup.edu/purchasing/public-postings/advertised-bids](http://www.lhup.edu/purchasing/public-postings/advertised-bids) Any questions regarding those may be addressed directly to Becky Proctor (LHUP) at 570-484-2010.

**GENERAL INFORMATION and CLARIFICATIONS:**

1. Any verbal questions or discussions are not official unless confirmed in writing via Addendum.
2. Clarification – LHUP will issue a Letter of Intent related to long lead equipment as necessary to expedite delivery of such equipment.
3. Clarification – LHUP may designate two existing Unit Ventilators as “salvage items”. If so, the (.2) Contractor shall disconnect/remove those undamaged and move them to a designated exterior location for pickup by LHUP. Otherwise, remove and dispose of units.

**REFERENCE THE SPECIFICATION BY SECTION & PAGE NUMBER**

- 01010-6 Add to paragraph 10.3.A: “The Contractor shall perform work which causes disruptive noise or vibration to First Floor occupants between 5am and 8am or after 5pm.”
- 15023, 15033, 15042, 15520: Refer to attached Sections which include all pages (some Specification books were printed with pages missing).

**REFERENCE THE DRAWINGS BY DRAWING NUMBER:**

- ME-101 (.4) CONTRACTOR: Add circuiting note at new exterior duplex receptacle shown near CU-2: “provide (2)#12 plus ground in 3/4” conduit to Panel ‘BC’ and connect to spare 20/1 breaker”.
- ME-101 (.2) CONTRACTOR: Revise Detail 3 (Pad Detail) per attached Sketch
- ME-101 (.2) CONTRACTOR: Revise the routing of refrigerant pipes from CU-2 and 3 which are shown running through the room labeled “Office”; run the pipes out to the Corridor parallel to the other pipes and then back into the Telecom closet to the riser point. Also, note that installation of the condensate drain pipe above the same Office ceiling shall be scheduled during unoccupied hours (5am to 8am or after 5pm).
- ME-102 (.4) CONTRACTOR: In each new Unit Ventilator, provide a single-pole toggle switch power to serve as disconnect switch.

**ATTACHMENT: REVISED DETAIL 3, SPECIFICATION SECTIONS 15023, 15033, 15042, 15520**

**END OF ADDENDUM NO. 1**